PT MERDEKA TSINGSHAN INDONESIA

STANDARD OPERATING PROCEDURE

PREPARATION OF THE CALCIUM CHLORIDE SOLUTION POST

氯化钙溶液制备岗位

MTI-CHP-CPM-SOP-007_Rev. 000

Information Security Classification
B – Business Information

Rev.	Revision Status	Date	Prepared by	Reviewed by	Approved by
0	Issued for Use	24-APR-2024	*Approval as attached*	*Approval as attached*	*Approval as attached*
C0	Issued for Approval	24-APR-2024	Song Yuhua	Li Jianjun	Clark Wu
B0	Issued for Review	24-APR-2024	Song Yuhua	Li Jianjun	
A0	Issued for Internal Discipline Review	24-APR-2024	Song Yuhua		

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

DOCUMENT CHANGE STATUS

No.	Page	Section	Change Log	Revision by	Revision date	Revision version
1.						
2.						
3.						

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

Table of Contents

DOCUMENT CHANGE STATUS 2
Table of Contents 3
1. Purpose 目的 4
2. Functional Description 功能说明 4
3. References 参考 4
4. PPE 个人保护装备 5
5. Hazards & Control 危害与控制 5
6. Equipment 工具/ 设备 6
7. Procedure 程序 6
8. Preparation of the Calcium Chloride Solution Post 氯化钙溶液制备岗位 Questionnaire 16
9. Appendix 17

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

1. Purpose 目的

This procedure covers the operator's responsibility for visual inspection, start up and shutdown preparation of the calcium chloride solution post under complete closure.

此程序涵盖操作员对完全关闭下的氯化钙溶液制备岗位进行目视操作前检查、启动运行和停车的责任。

2. Functional Description 功能说明

It is the responsibility of the operator to ensure that preparation of the calcium chloride solution post is visually inspected before and after each shift to determine whether it can start and operate safely, or whether other activities (such as maintenance and repair or other operator tasks) must be performed before starting, to determine the sequential operation method preparation of the calcium chloride solution post and smooth operation, Stop order of normal stops and emergency stops.

操作员有责任确保在从停机启动之前和每个班次开始时对氯化钙溶液制备岗位进行目视检查，确定是否可以启动并安全运行，或者是否必须在开始启动之前执行其他活动(例如维护修理或其他操作员任务)，确定氯化钙溶液制备岗位的按照顺序启动的操作方法及平稳运行，正常停车和紧急停车的停止顺序。


3. References 参考

- MTI-CP-SOP-Post Technical Operation Procedures.
  MTI-CP-SOP岗位操作规程
- Manual Ton Bag Breaker(4307-BBK-001).
  吨袋拆袋机(4307-BBK-001)
- Clean CaCl2 Solution Storage Tank(4307-TNK-004).
  浓氯化钙清液储槽(4307-TNK-004)
- Clean CaCl2 Solution Pump(4307-PSO-003/004).
  浓氯化钙清液泵(4307-PSO-003/004)
- CaCl2 Solution Preparation Tank(4307-TNK-005).
  氯化钙溶液制备槽(4307-TNK-005)
- Calcium Chloride Preparation Delivery Pump(4307-PSO-011/012).
  氯化钙制备输送泵(4307-PSO-011/012)
- Return Water Tank(4402-TNK-016).
  回水槽(4402-TNK-016)
- Calcium Chloride Solution Delivery Pump(4307-PSO-013/014).
  浓氯化钙溶液输送泵(4307-PSO-013/014)

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

4. PPE 个人保护装备





5. Hazards & Control 危害与控制

Description of Hazard / Environmental Issue 危害	Control Strategy 控制
1. Mechanical injury; 2. Dust; 3. Electric shock; 4. Slippery conditions and a trip to the danger; 5. Asphyxia; 6. Object falling from high altitudes; 7. Liquid sputtering; 8. Liquid sputtering; 9. Noise. 1. 机械伤害； 2. 灰尘； 3. 触电； 4. 湿滑的条件，绊倒危险； 5. 窒息； 6. 高空坠物； 7. 液体喷溅； 8. 液体腐蚀； 9. 噪音	1. Install a protective cover on the rotating part of the equipment; 2. Wear dust mask as required; 3. Do not contact the electrical switch with wet hands during operation, Regular inspection of the equipment leakage protection device is complete, effective; 4. Please hold the handrail up and down the stairs; 5. Clear clearance or maintenance operations; 6. Wear labor protection goods and check the safety of stacking items on the operation platform; 7. Wear protective masks and gloves, as well as other protective products as required; 8. Wear protective masks and gloves, as well as other protective products as required; 9. Wear the earplugs to protect your hearing. 1. 设备的转动部位安装防护罩； 2. 按要求佩戴防尘口罩； 3. 操作时不要湿手接触电器开关，定期检查设备漏电保护装置齐全、有效； 4. 上下楼梯请扶好扶手； 5. 清仓或维修作业执行审批程序； 6. 穿戴好劳保护品，检查各平台的物品堆

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

Description of Hazard / Environmental Issue 危害	Control Strategy 控制
	放安全性； 7. 按要求戴好防护面具和防护手套，以及其它劳保护品； 8. 穿戴适宜的劳保用品，一旦皮肤接触到有腐蚀的溶液，立即用大量清水冲洗； 9. 佩戴好耳塞，保护听力

6. Equipment 工具/ 设备

4307-AGT-001	Calcium Chloride Preparation Tank Agitrer 氯化钙制备槽搅拌器
4307-PSO-010	Submerged Pump液下泵
	Clean the site tools清扫现场工具

7. Procedure 程序

№	Stage	Key Points
1	General Check 普查	1. Confirm the pre-job technical training; 2. Wear suitable labor protection products, check and confirm that there is no unsafe state or safety risks on the site; 3. Check and clean the equipment and the site sanitation; 4. Contact with the process before and after and give clear instructions. 1. 确认经过岗前技术培训； 2. 穿戴好适合的劳保护品，检查确认现场没有存在不安全状态或安全隐患； 3. 检查并打扫设备、现场卫生； 4. 与前后工序取得联系，并发出明确指令
2	Inspect Manual Ton Bag Breaker(4307-BBK-001) 检查吨袋拆袋机(4307-BBK-001)	1. Check whether the cable connection is normal, whether the cable is damaged, and check whether the connection between the electrical box and the power connector is close; 2. Whether the power supply line is leakage; 3. Check whether the control box indicator light is normal and whether the sensitivity is normal; 5. Check whether the mechanical structure is normal, whether it is damaged or loose; 6. Check whether the lubrication of each component is normal, whether there is dust and foreign matter

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		affecting the work; 7. Check whether there is abnormal friction sound in the mechanical device, and if it should be stopped to avoid overload damage to the components; 8. Check the working condition of the electric hoist, whether the wire rope is broken, whether the hook is broken, and whether the hook and the hook are safe. 1. 检查电缆线连接是否正常，电缆是否损坏，检查电器箱与电源接头处的连接是否紧密； 2. 连接电源线路是否漏电； 3. 检查控制箱指示灯是否正常，灵敏度是否正常； 4. 检查机械结构是否正常，有无损坏、松动； 5. 检查各部件润滑是否正常，是否有灰尘、异物影响工作； 6. 检查机械装置是否有异常摩擦声，如有应停机排除，以免元件过载损坏； 7. 检查电动葫芦的工作情况，钢丝绳是否断线，吊钩是否断裂，吊钩与吊钩连接是否安全。
3	Inspect Clean CaCl2 Solution Storage Tank(4307-TNK-004), CaCl2 Solution Preparation Tank(4307-TNK-005), Return Water Tank (4402-TNK-016) 检查浓氯化钙清液储槽(4307-TNK-004)，氯化钙溶液制备槽(4307-TNK-005)，回水槽(4402-TNK-016)	1. Check whether the inlet and outlet pipelines and auxiliary pipelines, whether the installation of flange and valve meet the requirements, and whether the groove body is leaking liquid; 2. Check the level control assembly is normal. 1. 检查出入口管线及附属管线，法兰、阀门安装是否符合要求，槽体是否漏液； 2. 检查液位控制组件是否正常
4	Inspect Clean CaCl2 Solution Pump(4307-PSO-003/004), Calcium Chloride Preparation Delivery	1. Check whether the pump inlet pipeline and auxiliary pipeline, flange and valve installation meet the requirements, whether the anchor bolts and ground wire are good, and whether the coupling is installed; 2. Turn the pump shaft 3 times, should be flexible without

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
	Pump(4307-PSO-011/012), Calcium Chloride Solution Delivery Pump(4307-PSO-013/014) 检查浓氯化钙清液泵(4307-PSO-003/004)，氯化钙制备输送泵(4307-PSO-011/012)，浓氯化钙溶液输送泵(4307-PSO-013/014)	block; 3. Check whether the lubricating oil level is normal. The oil level should be between 1/2 and 2/3 of the oil lens; 4. Check the sealing condition of the pump is normal; 5. Point to move to confirm the correct steering; 6. Check whether the voltage meter, signal lamp and other meters of the pump control cabinet are normal; 7. Check whether the pump unit has air, if so, should be excluded; 8. Check Whether the pump head of concentrated calcium chloride solution pump (4307-PSO-003/004) is at the level of concentrated calcium chloride solution storage tank (4307-TNK-004), Whether the pump head of the preparation pump (4307-PSO-011/012) is at the level of the calcium chloride solution preparation tank (4307-TNK-005). 1. 检查泵出入口管线及附属管线，法兰、阀门安装是否符合要求，地脚螺栓及地线是否良好，联轴器及防护罩是否装好； 2. 手转动泵轴3圈，应灵活无阻滞； 3. 检查润滑油油位是否正常，油位应在油镜的1/2 ~ 2/3 之间； 4. 检查泵的密封状况是否正常； 5. 点动确认转向正确； 6. 检查泵控制柜电压表、信号灯等仪表指示是否正常； 7. 检查泵机组是否有空气，如有应予以排除； 8. 检查浓氯化钙清液泵(4307-PSO-003/004)泵头是否处于浓氯化钙清液储槽(4307-TNK-004)液位下，氯化钙制备输送泵(4307-PSO-011/012)泵头是否处于氯化钙溶液制备槽(4307-TNK-005)液位下
5	Check the other Equipment and Facilities 检查其它设备设施	1. Submerged pump(4307-PSO-010) a. Check whether there is debris in the lower pump tank and the pipeline blockage; b. Check whether the fastening screws of the equipment and motor are loose, whether the bearing is intact, and whether the lubricating oil is intact; c. Check whether the electrical part of the equipment is in good condition and whether the motor shell is well grounded; d. Check whether the steering of the motor is correct; e. Check whether the pump head is under the ground trough liquid level.

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		1. 液下泵(4307-PSO-010) a. 检查液下泵槽内有无杂物，管路堵塞情况； b. 检查设备、电机的紧固螺丝是否松动，轴承是否完好，润滑油是否完好； c. 检查设备电气部分是否完好，电机外壳是否接地良好； d. 检查电机的转向是否正确； e. 检查泵头是否处于地槽液位下。 2. Calcium Chloride Preparation Tank Agitrer(4307-AGT-001) a. Check whether the screws of the mixing paddle are fastened; b. Check whether the positive and reverse version of the agitator is correct; c. Check the surface of the mixer is smooth, without rough and pitting phenomenon; d. Check whether the mechanical seal of the mixer is good and whether the oil seal is normal; e. Electric mixer idling, check for abnormal sound, whether the up and down are concentric or shaking 2. 氯化钙制备槽搅拌器(4307-AGT-001) a. 检查搅拌桨的螺丝是否紧固； b. 检查搅拌器的正反转是否正确； c. 检查搅拌器的搅拌桨表面光滑，无粗糙和点蚀现象； d. 检查搅拌器的机械密封是否良好，各油封是否正常； e. 电动搅拌器进行空转，检查是否有异常声响，上下是否同心或摇晃。 3. Valve a. Check the one gate valve (65GA) of the concentrated calcium chloride solution reservoir (4307-TNK-004) from the middle water pump of sewage treatment(4711-PLO-100/101), Whether a butterfly valve (150BF) at the bottom drain is normal and flexible; b. Check the two butterfly valves (150BF, 150BF) at the inlet of the chloride pump (4307-PSO-003/004), Two butterfly valves (125BF, 125BF), Go to a butterfly valve (80BA) in the high clearance tank (4307-TNK-001), Whether a butterfly valve (125BF)

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		directed to the calcium chloride solution preparation tank (4307-TNK-005) is normal and flexible; c. Check the calcium chloride solution preparation tank (4307-TNK-005) from the reclaimed water pump (4711-PLO-100/101) (65GA), Whether a butterfly valve (150BF) at the bottom drain is normal and flexible; Check whether the two butterfly valves (150BF, 150BF) at the inlet pump (4307-PSO-011/012) and the two butterfly valves (125BF, 125BF) are normal and flexible; d. Check whether a butterfly valve (100BF) at the bottom of the return water tank (4402-TNK-016) is normal and flexible; e. Check whether two butterfly valves (125BF, 125BF) at the concentrated calcium chloride solution delivery pump (4307-PSO-013/014) and two ball valves (80BF) (80BF) are normal and flexible. 3. 阀门 a. 检查浓氯化钙清液储槽(4307-TNK-004)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA)，底部排液一个蝶阀(150BF)是否正常、灵活; b. 检查浓氯化钙清液泵(4307-PSO-003/004)入口两个蝶阀(150BF,150BF)，出口两个蝶阀(125BF,125BF)，去往高位清液槽(4307-TNK-001)的一个蝶阀(80BA)、去往氯化钙溶液制备槽(4307-TNK-005)的一个蝶阀(125BF)是否正常、灵活; c. 检查氯化钙溶液制备槽(4307-TNK-005)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA)，底部排液一个蝶阀(150BF)是否正常、灵活; d. 检查氯化钙制备输送泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，出口两个蝶阀(125BF,125BF)是否正常、灵活; 检查回水槽(4402-TNK-016)底部排液一个蝶阀(100BF)是否正常、灵活; e. 检查浓氯化钙溶液输送泵(4307-PSO-013/014)入口两个蝶阀(125BF,125BF)，出口两个蝶阀(80BF,80BF)一个球阀(80BA)是否正常、灵活。

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
6	Inspect Materials Level 检查物料料位	1. Check whether there is calcium chloride solution in concentrated calcium chloride solution storage tank (4307-TNK-004), calcium chloride solution preparation tank (4307-TNK-005) and return water tank (4402-TNK-016) with calcium chloride solution; 2. Check whether there are empty ton bags on the ton bag unpacking machine (4307-BBK-001). 1. 检查浓氯化钙清液储槽(4307-TNK-004)、氯化钙溶液制备槽(4307-TNK-005)和回水槽(4402-TNK-016)是否存有氯化钙溶液; 2. 检查吨袋拆袋机(4307-BBK-001)上是否有空吨袋
7	Start-Up preparation of calcium chloride solution Post 氯化钙溶液制备岗位开机	1. No-load start should be guaranteed when starting; 2. The driving sequence is along the material direction, from back to front that is the reverse drive, Each equipment needs to be switched on later;At the same time, Confirm that the process behind the calcium chloride solution post has been started and has the feeding conditions: Open the one gate valve (65GA) of the concentrated calcium chloride solution storage tank (4307-TNK-004) from the middle water pump of sewage treatment (4711-PLO-100/101) to fill the medium water Start the calcium chloride preparation tank mixer(4307-AGT-001) Open the control bag holder in the ton bag unpacking machine, and lift the calcium chloride ton bag by the electric hoist Lift the ton bag to the preparation tank of calcium chloride solution, extend the feeding port of the ton bag into the feeding port of the calcium chloride solution preparation tank, untie the rope of the cutting port, press the bag plate and completely press the bag mouth, so that the calcium chloride in the bag can flow into the calcium chloride solution preparation tank When there is about 1 / 3 of the calcium chloride in the bag, open the control valve of the beating device and push all the calcium chloride around the bag to the middle feeding position After the calcium chloride discharge, the cutting port is tightened, the bag board is slowly raised, the empty ton bag is removed, the unpacking work is completed, and the ton bag electric hoist is opened to the designated position and anchored Prepare the calcium chloride solution, open the calcium chloride preparation delivery pump (4307-PSO-011/012) and exit two butterfly valves (125BF, 125BF) as required, Start the calcium chloride preparation pump (4307-PSO-011/012), open two butterfly valves (150BF, 150BF) at the calcium chloride preparation pump (4307-

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		PSO-011/012), Transfer the calcium chloride solution to the return tank (4402-TNK-016) for storage As required, open the concentrated calcium chloride solution delivery pump (4307-PSO-013/014) outlet two butterfly valves (80BF, 80BF) one ball valve (80BA), Start the delivery pump (4307-PSO-013/014), Open two butterfly valves (125BF, 125BF) at the inlet of the concentrated calcium chloride solution delivery pump (4307-PSO-013/014), Transfer the concentrated calcium chloride solution to the corresponding post Open two butterfly valves (125BF, 125BF) for calcium chloride delivery pump (4307-PSO-011/012), Start the delivery pump (4307-PSO-011/012), Open the two butterfly valves (150BF, 150BF) (4307-PSO-011/012), Transfer the calcium chloride solution to the high-level clearing tank (4307-TNK-001) or the calcium chloride solution preparation tank (4307-TNK-005). 1. 启动时应保证空载启动； 2. 开车顺序为沿物料走向，从后往前开即逆向开车，各设备都需要延时开启；同时，确认氯化钙溶液制备岗位后面的工序已经开车并具备给料条件： 打开浓氯化钙清液储槽(4307-TNK-004)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA)，注满中水 启动氯化钙制备槽搅拌器(4307-AGT-001) 将吨袋拆袋机中的控制夹袋器打开，夹住氯化钙吨袋由电动葫芦吊起 吊吨袋至氯化钙溶液制备槽上方，吨袋下料口伸入氯化钙溶液制备槽进料口内，解开下料口扎袋绳索，同时将夹袋板下压、把袋口完全压紧，使袋内的氯化钙流入氯化钙溶液制备槽 吨袋内氯化钙剩下约1/3时，将拍打装置控制阀打开，把吨袋内周边的氯化钙全部推到中间下料口位置 氯化钙卸完后，将下料口扎紧，夹袋板缓缓升起，后将空吨袋去除，完成拆包工作，后将吨袋电动葫芦开到指定位置并锚住 氯化钙溶液制备完成，根据需要，打开氯化钙制备输送泵(4307-PSO-011/012)出口两个蝶阀(125BF,125BF)，启动氯化钙制备输送泵(4307-PSO-011/012)，打开氯化钙制备输送

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，将氯化钙溶液输送到回水槽(4402-TNK-016)储存 根据需要，打开浓氯化钙溶液输送泵(4307-PSO-013/014)出口两个蝶阀(80BF,80BF)一个球阀(80BA)，启动浓氯化钙溶液输送泵(4307-PSO-013/014)，打开浓氯化钙溶液输送泵(4307-PSO-013/014)入口两个蝶阀(125BF,125BF)，将浓氯化钙溶液输送到相应的岗位打开氯化钙制备输送泵(4307-PSO-011/012)出口两个蝶阀(125BF,125BF)，启动氯化钙制备输送泵(4307-PSO-011/012)，打开氯化钙制备输送泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，输送氯化钙溶液去往高位清液槽(4307-TNK-001)或氯化钙溶液制备槽(4307-TNK-005)。
8	The preparation of calcium chloride solution Post Stops 氯化钙溶液制备岗位停机	1. Orderly shutdown a. The materials in the standby machine should be discharged before stopping; b. Stop in reverse order of driving order , Each equipment needs to stop: Close two butterfly valves (125BF) (4307-PSO-003/004) (125BF), Stop (4307-PSO-003/004), Close the concentrated calcium chloride solution delivery pump (4307-PSO-003/004) outlet of two butterfly valves (80BF, 80BF) and one ball valve (80BA) Close the two butterfly valves (150BF, 150BF) (4307-PSO-011/012), Stop the delivery pump (4307-PSO-011/012), Close two butterfly valves (125BF,125BF) of calcium chloride preparation pump (4307-PSO-011/012) Close the two butterfly valves (150BF, 150BF) (4307-PSO-011/012), Stop the delivery pump (4307-PSO-011/012), Close two butterfly valves (125BF,125BF) of calcium chloride preparation pump (4307-PSO-003/004) Stop the calcium chloride preparation tank mixer(4307-AGT-001) Close the reservoir (4307-TNK-004) from the reclaimed water pump (4711-PLO-100/101) (65GA) Clean the site for hygiene. 1. 正常停车 a. 停车时应待机内物料排净后再停车； b. 按照开车顺序逆序顺序停车，各设备都需要延

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		时停止： 关闭浓氯化钙清液输送泵(4307-PSO-003/004)入口两个蝶阀(125BF,125BF)，停止浓氯化钙清液输送泵(4307-PSO-003/004)，关闭浓氯化钙清液输送泵(4307-PSO-003/004)出口两个蝶阀(80BF,80BF)一个球阀(80BA) 关闭氯化钙制备输送泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，停止氯化钙制备输送泵(4307-PSO-011/012)，关闭氯化钙制备输送泵(4307-PSO-011/012)出口两个蝶阀(125BF,125BF) 关闭氯化钙制备输送泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，停止氯化钙制备输送泵(4307-PSO-011/012)，关闭氯化钙制备输送泵(4307-PSO-011/012)出口两个蝶阀(125BF,125BF) 停止氯化钙制备槽搅拌器(4307-AGT-001) 关闭浓氯化钙清液储槽(4307-TNK-004)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA) 打扫现场卫生。 2. Emergency Stop a. When an emergency occurs, close clean CaCl2 solution pump(4307-PSO-003/004), calcium chloride preparation delivery pump(4307-PSO-011/012), calcium chloride solution delivery pump(4307-PSO-013/014) and calcium chloride preparation tank agitator(4307-AGT-001); After all stop the operation, Check whether the start / stop button of each device is in the stop state, Close a solution (4307-TNK-004) from (4711-PLO-100/101) (65GA); Calcium chloride solution preparation tank (4307-TNK-005), pumped from the reclaimed water pump (4711-PLO-100/101); Calcium chloride preparation delivery pump (4307-PSO-011/012) inlet two butterfly valves (150BF, 150BF), outlet two butterfly valves (125BF, 125BF); The pump (4307-PSO-003/004), two butterfly valves (150BF, 150BF), two butterfly valves (125BF, 125BF); Concentrated calcium chloride solution delivery pump (4307-PSO-013/014) inlet two butterfly

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

№	Stage	Key Points
		valves (125BF, 125BF), outlet two butterfly valves (80BF, 80BF) one ball valve (80BA); at the same time, the upper level of equipment all need to stop; b. After the accident, the equipment is restored to normal. If production still needs to be conducted, the operation shall be restarted in the driving sequence; c. After the accident treatment, the equipment returns to normal. If the production is not necessary, operate according to the normal parking order 2. 紧急停车 a. 当出现紧急事故，关闭浓氯化钙清液泵(4307-PSO-003/004) 、氯化钙制备输送泵(4307-PSO-011/012)、浓氯化钙溶液输送泵(4307-PSO-013/014)和氯化钙制备槽搅拌器(4307-AGT-001)；全部停止运行后，检查各设备的启动/停止按钮是否处于停止状态，关闭浓氯化钙清液储槽(4307-TNK-004)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA)；氯化钙溶液制备槽(4307-TNK-005)来自污水处理的中水泵(4711-PLO-100/101)泵过来的中水一个闸阀(65GA)；氯化钙制备输送泵(4307-PSO-011/012)入口两个蝶阀(150BF,150BF)，出口两个蝶阀(125BF,125BF)；浓氯化钙清液泵(4307-PSO-003/004)入口两个蝶阀(150BF,150BF)，出口两个蝶阀(125BF,125BF)；浓氯化钙溶液输送泵(4307-PSO-013/014)入口两个蝶阀(125BF,125BF)，出口两个蝶阀(80BF,80BF)一个球阀(80BA)；同时，上一级设备均需停车； b. 事故处理后，设备恢复正常，如仍需要进行生产，按照开车顺序重新启动操作； c. 事故处理后，设备恢复正常，如不需要进行生产，按照正常停车顺序进行操作
9	Permits &Isolation Sheets 许可证和隔离表	1. Only authorized isolators can sign off and cancel permits and registration sheets. 1. 只有经过授权的隔离者才能签署和取消许可证和登记表。

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

8. Preparation of the Calcium Chloride Solution Post 氯化钙溶液制备岗位 Questionnaire

Declaration of Understanding

I (_____ Learner _____) have completed the theory assessment and had all my valid, reliable, and consistent with my level of knowledge in the assessment task.

Signature
Date:

I (_____ Assessor _____) have witnessed the above learner complete the theory assessment and believe the assessment has provided a valid, reliable, and consistent result.

Signature
Date:

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

9. Appendix

This publication may not be reproduced, stored in the system, transferred in any form by any means, electronic, mechanical, photocopying, recorded, or otherwise without the permission of PT. Merdeka Tsingshan Indonesia.

Standard Operating Procedure
标准操作程序

Calcium chloride solution posts in the chloride plant
CP 氯化钙溶液制备岗位

SOP Details 程序明细

Processing Department 氯化厂	Procedure Level 程序级别: **3**	Revision Number 修订编号: 0
Date Approved 审批日期:	Date Issued 颁布日期:	Next Review Date 下次审核日期:
Details of Revision 修订明细:		

Revision Details 修订明细

Rev. No 版本号	Date 日期	Section 章节	Page 页码	Revision Description 修订说明	Reviewed By 审核人
1					
2					
3					

Approvals 批准

Document Owner 程序持有人	Song Yuhua 宋裕华	Date: 日期: 2024.4.24	Signature 签字	
Processing Superintendent 氯化高级副经理	Cao Guibin 曹桂宾	Date: 日期: 2024.4.24	Signature 签字	
Processing Senior Manager 氯化高级经理	Li Jianjun 李建军	Date: 日期: 2024.04.24	Signature 签字	
Safety Department Manager 安全部经理	Airlangga Putra R.J	Date: 日期: 24.04.24	Signature 签字	
Deputy General Manager 副总经理	Li Xinhua 李新华	Date: 日期 2024.4.24	Signature 签字	
General Manager 总经理	Clark Wu 吴迎林	Date: 日期: 2024.4.24	Signature 签字	